

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 207
WICHITA, KANSAS 6720

API Well Number: ~~15-159-24251-00-00~~ ²¹⁴¹³⁻⁰⁰⁻⁰⁰
Spot: N2N2NW Sec/Twnshp/Rge: 6-21S-6W
4884 feet from S Section Line, 3944 feet from E Section Line
Lease Name: WILLHAUS Well #: 4
County: RICE Total Vertical Depth: 3540 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

PROD Size: 4.5 feet: 3535 175 SX CMT
SURF Size: 8.625 feet: 222 185 SX CMT

8115⁰⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/11/2004 11:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: Sand to 3,425' & top with 4 sxs. cement. Shoot casing off. Pull casing to 1,050' & spot 35 sxs. cement. Pull casing to 625' & spot 35 sxs. cement. Pull casing to 275' & circulate cement to the surface.

Plugging Proposal Received By: MICHAEL WILSON
Date/Time Plugging Completed: 06/11/2004 3:00 PM

WitnessType: NONE
KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Sanded to 3,425' & topped with 4 sxs. cement. Shot casing off at 1,800'. Pulled casing to 1,036' & spotted 35 sxs. cement w/100# hulls. Pulled casing to 634' & spotted 35 sxs. cement w/200# hulls. Pulled casing to 312' & circulated 100 sxs. cement to the surface.

Perfs:

Top	Bot	Thru	Comments
3500	3504		
3476	3480		

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 21 2004
CONSERVATION DIVISION
WICHITA, KS

RECEIVED
KCC DISTRICT #2
JUN 17 2004
WICHITA, KS

Remarks: USED 60/40 POSMIX W'4% GEL BY COPELAND ACID & CEMENTING. INVOICE #24492.

Plugged through: CSG

District: 02

Signed Michael Wilson
(TECHNICIAN)

INVOICED

DATE 6-21-04

TEL NO 200-406-1755