

KANSAS

Form CP-3

Rev. 6-4-68

STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

JUN 29 1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-039-20162-00-00

CONSERVATION DIVISION
Wichita, Kansas

6-29-70

Operator's Full Name Stoeppelwerth Drilling, Incorporated.

Complete Address Box #193, Russell, Kansas.

Lease Name Simpson Well No. 1

Location SW-SE Sec. 10 Twp. 2 Rge. XXX(E) (W) 27

County Decatur Total Depth 4005'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 7:15 PM Day 26 Month 6 Year 1970

The above well was plugged as follows:

246'--8 5/8--Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1114'.

Circulated hole with heavy mud. Pulled DP to 1375' and displaced 100 Sx. cement thru
DP from 1375' to 1050'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 6/30/70

INV. NO. 2144-W