



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-039-20293-00-00

RECEIVED
STATE CORPORATION COMMISSION

OCT 21 1974

CONSERVATION DIVISION
Wichita, Kansas

10-21-74

Operator's Full Name Dane G. Hansen Trust,
Complete Address Box #187, Logan, Kansas.
Lease Name Macfee Well No. 1
Location NW-NW Sec. 8 Twp. 2 Rge. (E) (W) 27
County Decatur Total Depth 3250'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor C & G Drilling Company,

Address 1107 Union Nat'l Bldg., Wichita, License No.

Operation Completed: Hour 9:45 PM Day 15 Month 10 Year 1974

The above well was plugged as follows:

261'--8 5/8" Surface casing, cement circulated with 165 Sx.
Top of Dakota section @ 900'.

Circulated hole with heavy mud. Pulled DP to 1125' and displaced 110 Cu. Ft. cement
thru DP from 1125' to 800'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: A. L. Dickels
Well Plugging Supervisor

INVOICED

DATE 10/23/74

INV. NO. 157-W