

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-039-20208-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 24 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
5-24-71

Operator's Full Name Donald C. Slawson,

Complete Address 408 One-Twenty Building, Wichita, Kansas.

Lease Name Uehlin Well No. A-2

Location 160' N & 120' E of CSW-NE Sec. 7 Twp. 2 Rge. (E) (W) 27

County Decatur Total Depth 3422'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Slawson Drilling Company, Incorporated,

Address 408 One-Twenty Building, Wichita, Kansas. License No.       

Operation Completed: Hour 3:30 PM Day 17 Month 5 Year 1971

The above well was plugged as follows:

277'--8 5/8" Surface casing, cement circulated with 300 Sx.  
Top of Dakota section @ 1075'.

Circulated hole with heavy mud. Pulled DP to 1300' and displaced 100 Sx. cement thru  
DP from 1300' to 975'. Pulled DP to 300' and displaced 25 Sx. cement thru DP from  
300' to 225'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols  
Well Plugging Supervisor

DATE 5-24-71

INV. NO. 3743-10