

KANSAS

X
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20209-00-00

RECEIVED
STATE CORPORATION COMMISSION
MAY 27 1971
CONSERVATION DIVISION
Wichita, Kansas
5-27-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Donald C. Slawson,
Complete Address 408 One-Twenty Building, Wichita, Kansas.
Lease Name Uehlin Well No. C-1
Location CSW-SE Sec. 6 Twp. 2 Rge. (E) (W) 27
County Decatur Total Depth 3565'.
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Slawson Drilling Company, Incorporated,
Address 408 One-Twenty Building, Wichita, Kansas. License No.
Operation Completed: Hour 2:30 Am Day 23 Month 5 Year 1971

The above well was plugged as follows:

315'--8 5/8" Surface casing, cement circulated with 250 Sx.
Top of Dakota section @ 1125'.

Circulated hole with heavy mud. Pulled DP to 1350' and displaced 100 Sx. cement thru
DP from 1350' to 1025'. Pulled DP to 350' and displaced 25 Sx. cement thru DP from
350' to 275'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/27/71
INV. NO. 3760-U

Signed: M. L. Nichols
Well Plugging Supervisor