

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20134-00-00

RECEIVED
STATE CORPORATION COMMISSION
DEC 22 1969
CONSERVATION DIVISION
Wichita, Kansas
12-22-69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name John O. Farmer, Incorporated,

Complete Address 370 West Wichita Avenue, Russell, Kansas.

Lease Name Bogart Well No. 1

Location CNE-SW Sec. 5 Twp. 2 Rge. (E) (W) 27

County Decatur Total Depth 3465'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 6:45 AM Day 18 Month 12 Year 1969

The above well was plugged as follows:

136'--8 5/8" Surface casing, cement circulated with 115 Sx.
Top of Dakota section @ 975'.

Circulated hole with heavy mud. Pulled DP to 1175' and displaced 100 Sx. cement thru
DP from 1175' to 850'. Pulled DP to 150' and displaced 25 Sx. cement thru DP from
150' to 75'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. S. Nichols
Well Plugging Supervisor

INVOICED
DATE 12-22-69
INV. NO. 1092-W