

15-039-00032-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

WELL PLUGGING APPLICATION FORM

File One Copy

Lease Owner Brooks Hall Address 1499 Oklahoma City, Okla.
(Applicant)

Lease (Farm Name) Odle Well No. #1

Well Location NW-NW-SE Sec. 1 Twp. 2 Rge. 26 (E)-(W) W

County Decatur Field Name (if any) Wildcat

Total Depth 3833 Ft. Oil Gas Dry Hole Dry Hole

Was well log filed with application? yes. If not, explain: _____

Date and hour plugging is desired to begin 4-16-52 8:00 A. M.

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission, or with the approval of the following exceptions: Explain fully any exceptions desired.
(Use an additional sheet if necessary) _____

Name of the person on the lease in charge of well for owner _____

T. C. Strain Address Box 188 Hays, Kansas

Name of Plugging Contractor Strain Drilling Co.

Address Box 188, Hays, Kansas

Invoice covering assessment for plugging this well should be sent to

Benson-Montin, Inc. Address Petroleum Building, Oklahoma City
Oklahoma

and payment will be guaranteed by applicant.

APR 19 1952
PLUGGING
FILE SEC 14-T-2-R-26c
BOOK PAGE 9 LINE 25 4-19-52

T. C. Strain
T. C. Strain
Applicant or Acting Agent

Date April 18, 1952



15-039-00032-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

April 18, 1952

Well No. 1
Lease Odle
Description N. M. SE Sec. 11-2-26W
County Decatur
File No. 9-25

Benson & Montin, Inc.,
Petroleum Building
Oklahoma City, Oklahoma

Gentlemen:

This letter is your authority to plug the above subject well, in accordance with the Rules and Regulations of the State Corporation Commission. When you are ready to plug this well, please contact our District Plugging Supervisor, Mr. Eldon Petty, Box 326, Hays, Kansas.

STATE CORPORATION COMMISSION
CONSERVATION DIVISION

BY: J. P. Roberts
J. P. ROBERTS

cc: DISTRICT PLUGGING SUPERVISOR

15-039-00032-00-00

WELL LOG

COMPANY: Brooks Hall & Strain Drilling Co.

NW-NW-SE Sec. 14
Twp. 2, Rge. 26 Decatur County,
Kansas

LEASE: Odle #1

ELEVATION: 2538

NOTE: Allmeas. Rotary bushings

0	50 Soil & shale
50	120 Sand
120	170 Sandy Lime
170	225 Br Shale
225	372 Blue Shale
372	600 Blue Shale
600	1365 Shale Shell & Sand
1365	1480 Shale Shells & Pyrite
1480	1600 Shale
1600	1700 Shale Redbed
1700	1770 Sand Hard
1770	1800 Shale & Sand
1800	1925 Shale & Shells
1925	2025 Shale & Redbed
2025	2065 Anhydrite
2065	2068 Shale & Shells
2068	2300 Shale & Shells
2300	2435 Shale & Shells
2435	2500 Lime Shale
2500	2520 Lime & Shale
2520	2695 Shale & Shells
2695	2815 Lime & Shale & Pyrite
2815	2870 Lime Hard
2870	2930 Lime & Pyrite
2930	3000 Shale & Lime
3000	3120 Shale & Shale
3120	3190 Shale & Lime
3190	3280 Lime
3280	3360 Lime & Shale
3360	3390 Lime
3390	3409 Lime
3409	3430 Lime
3430	3480 Lime

3480	3505 Lime
3505	3575 Lime & Shale
3575	3625 Lime
3625	3675 Lime & Shale
3675	3723 Shale & Lime
3723	3742 Red Shale & Lime
3742	3765 Arbuckle
3765	3783 Granite Wash
3783	3825 Granite
3825	3833 Granite Wash
3833	(Total Depth) R. B.

COMMENCED 4-5-52
COMPLETED 4-16-52

Casing Record

8 5/8 Surface Casing set at 169' w/100 sacks of cement by Globe Cementing Co.

D. S. T.

3394-3409' Tool open 1 hour Recovered 55 feet Drilling mud. B.H.P. 1100#.

Schlumberger Log to T. D.

Geologist Jake Lemon

TOPS: Geological Tops

Anhydrite	2025	T. D.	3833	Lansing, K.C.	3333
Howard	3140			Base K. C.	3546
Topeka	3185			Arbuckle	3742
Heebner	3290			Granite Wash	3783
Toronto	3319			Granite	3831

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Odle #1, located NW-NW-SE, Sec. 14, T. 2, R. 26 Decatur County, Kansas

CONTRACTOR: Strain Drilling Co.

By *T. C. Strain*
T. C. Strain

PLUGGING
FILE SEC 14 T 2 R 26 W
BOOK PAGE 9 LINE 25

Subscribed and sworn to before me this 18th day of April 1952

Mildred Schneider

My commission expires March 26, 1956

479-52