

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
P. O. BOX 17027  
WICHITA, KANSAS 67217

Rev. 6-3-74  
FORM CP-1

RECEIVED  
STATE CORPORATION COMMISSION

APR 23 1976  
4-23-76  
CONSERVATION DIVISION  
Wichita, Kansas

WELL PLUGGING APPLICATION FORM  
File One Copy

API Number 15 - 039 - 20, 327 - 0000 (of this well)  
Lease Owner Midwest Energy, Inc.  
Address 8268 Hascall Street, Omaha, Neb. 68127  
Lease (Farm Name) SCHWAB Well No. #1  
Well Location C NE NW Sec. 7 Twp. 2S Rge. (E) 26 (W)  
County Decatur Total Depth 3780' Field Name \_\_\_\_\_  
Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ Rotary D & A X  
Well Log attached with this application as required Yes  
Date and hour plugging is desired to begin 9:30 p.m. April 16, 1976

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Joe Weber Address Ellis, Kansas 67637

Plugging Contractor Abercrombie Drilling, Inc. License No. #746

Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:

Name Midwest Energy, Inc.

Address 8268 Hascall Street, Omaha, Nebraska 68127

and payment will be guaranteed by applicant or acting agent.

Signed: Jerry A. Langrehr  
Applicant or Acting Agent

Date: April 22, 1976

State of Kansas



15-039-20327-00-00

*State Corporation Commission*

**CONSERVATION DIVISION**

(Oil, Gas and Water)

245 North Water  
WICHITA, KANSAS 67202

April 20, 1976

**WELL PLUGGING AUTHORITY**

Well No.	1
Lease	Schwab
Description	C NE NW Sec. 7-2-26W
County	Decatur
Total Depth	3780
Plugging Contractor	Abercrombie Drilling Co.


Midwest Energy, Inc.  
8268 Hascall Street  
Omaha, NB 68124

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,

  
J. Lewis Brock, Administrator

Mr. Gilbert Balthazor, P. O. Box 9, Rt. #1, Palco, KS 67657  
is hereby assigned to supervise the plugging of the above named well.

CONTRACTOR'S WELL LOG

OPERATOR: Midwest Energy, Inc.  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: SCHWAB #1  
 LOCATION: C NE NW Section 7-2S-26W  
 Decatur County, Kansas  
 SPUD DATE: April 7, 1976  
 COMPLETION DATE: April 16, 1976

0	40	Clay
40	190	Sand
190	1100	Shale
1100	1200	Dakota Sand
1200	1760	Shale
1760	1858	Cedar Hills Sand
1858	2074	Shale
2074	2102	Anhydrite
2102	2365	Shale
2365	3417	Shale & Lime
3417	3778	Lime
	3778	Rotary Total Depth

SAMPLE TOPS:	ELEVATION:
Anhydrite 2074'	2607' G.L.
B/Anhydrite 2102'	2615' K.B.

Cut 217' of 12 1/4" hole. Ran 5 jts. 8 5/8" casing, Set @ 217' K.B. Tallied 207'. Cemented with 160 sx. Quick-Set cement. Plug was down @ 7:00 p.m. April 7, 1976.  
 Plugged and Abandoned: 1st Plug was Set @ 1150' with 70 sx. cement; 2nd Plug was Set @ 200' with 20 sx. cement; 3rd Plug was Set @ 40' with 10 sx. cement. State Plugger: Gilbert Balthazor - Plug was down @ 9:30 p.m. April 16, 1976.

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

Jerry A. Langrehr, Executive Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the SCHWAB #1, C NE NW Section 7-2S-27W, Decatur County, Kansas.

ABERCROMBIE DRILLING, INC.

*Jerry A. Langrehr*  
 Jerry A. Langrehr - Exec. Vice President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 22nd day of April, 1976.

*Diane Steincamp*  
 Diane Steincamp - Notary Public

My Commission Expires: February 18, 1980

