

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION

FORM CP-1

Rev. 03/92

130 S. Market, Room 2078  
Wichita, Kansas 67202

RECEIVED  
JUN 24 2004  
KCC WICHITA

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

API #: 15-159-22421-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spu or completion date

WELL OPERATOR: RAMA Operating Co., Inc. KCC LICENSE # 3911  
(owner/company name) (operator's)

ADDRESS: P.O. Box 159 CITY: Stafford  
STATE: Kansas ZIP CODE: 67578 CONTACT PHONE: 620-234-5191  
LEASE: Wellman Ranch WELL#: No. 3 Section 28 Township 21s Range 9w  
W/2 Nw Sw SPOT LOCATION/QQQQ COUNTY: Rice

1980 FEET (in exact footage) FROM South LINE OF SECTION (NOT Lease Line)  
330 FEET (in exact footage) FROM West LINE OF SECTION (NOT Lease Line)

Check One: Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ D&A XX SWD/ENHR WELL \_\_\_\_\_ Docket # \_\_\_\_\_  
CONDUCTOR CASING SIZE None SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS  
SURFACE CASING SIZE 8-5/8" SET AT 238' KB CEMENTED WITH 225 SACKS  
PRODUCTION CASING SIZE None SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:  
ELEVATION 1689 G.L. 1698 K.B. T.D. 3536 PBTD \_\_\_\_\_ Anhydrite Depth 296-315  
(Stone Corral Formation)  
CONDITION OF WELL: GOOD XX POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

PROPOSED METHOD OF PLUGGING:  
Received plugging orders 6/22/04 from Steve VanGieson. Plugged using 130 sx of 60/40 Poz; 6% Gel.  
Heavy mud in hole and between all plugs. Bottom plug @ 1300'/35sx; 2nd plug @ 900'/35sx; 3rd plug @ 290'/35sx; top plug at 60'/10 sx cemented to surface. Plugged rathole/15sx; no mousehole.  
Plug down at 1:15 pm, 6/22/04. Allied ticket # 17914. Reported to KCC 6/22/04.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes (YES,NO) IS ACO-1 FILED? ? (YES,NO)  
If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Name: Gary Pugh/Gary M. Talbott Phone#: (620) 672-9508  
Address: P.O. Box 1006 City: Pratt State: Kansas  
PLUGGING CONTRACTOR: Sterling Drilling Company KCC LICENSE #: 5142  
(company name) (contractor's)  
Address: P.O. Box 1006 City: Pratt State: Kansas Zip 67124

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Plugged well at 1:15 pm on June 22, 2004  
PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY: Operator X Agent \_\_\_\_\_

DATE: 06/22/04 AUTHORIZED OPERATOR OR AGENT: Gary M. Talbott  
(signature) Gary M. Talbott, Agent for Operator

# Sterling Drilling Company, Rig #1

Box 1006, Pratt, Kansas 67124-1006  
Office Phone (620) 672-9508, Fax 672-9509

## SAMPLE LOG

## Wellman Ranch No. 3

**LOCATION:** W/2 Nw Sw  
**API:** 15-159-22421-0000

Section 28 T 21s R 9w  
Rice County, Kansas

**OWNER:** RAMA Operating Co., Inc.  
**CONTRACTOR:** Sterling Drilling Company, Rig #1

**COMMENCED:** 16-Jun-04  
**COMPLETED:** 22-Jun-04

**TOTAL DEPTH:** **DRILLER** 3536 FEET  
**LOGGER** No Logs FEET

**Ground Elevation:** 1689  
**KB Elevation:** 1698

### LOG

0 -	15 FEET	Top Sand
15 -	25 FEET	Clay
25 -	72 FEET	Sand and Gravel
72 -	296 FEET	Redbeds and Shales
296 -	315 FEET	Anhydrite (Driller's)
315 -	1250 FEET	Shales and Salt
1250 -	3536 FEET	Limestone/Shale and Dolomite

RECEIVED  
JUN 24 2004  
KCC WICHITA

### CASING RECORDS

#### Surface/Production Casing Data:

Spud at 3:45 pm on 06-16-04. Drilled 12 1/4" hole to 242'. Ran 6 joints of new 23#, 8-5/8" surface casing. Tallied 242' set at 238' KB. Cemented with 225 sacks 70/30 Poz, 2% Gel, 3% CC. Cement did circulate. Plug down at 10:15 pm on 06-16-04 by Allied Cementing. Ticket # 13005.

#### Plugging Data:

Received plugging orders 6/22/04 from Steve VanGieson. Plugged using 130 sx of 60/40 Poz; 6% Gel. Heavy mud in hole and between all plugs. Bottom plug @ 1300'/35sx; 2nd plug @ 900'/35sx; 3rd plug @ 290'/35sx; top plug at 60'/10 sx cemented to surface. Plugged rathole/15sx; no mousehole. Plug down at 1:15 pm, 6/22/04. Allied ticket # 17914. Reported to KCC 6/22/04.

### DEVIATION SURVEYS

1/2 degree(s) at 242 feet  
2-1/4 degree(s) at 3536 feet