



15-039-80162-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 29 1970
CONSERVATION DIVISION
Wichita, Kansas

6-29-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Geo. Stoepfelwerth of Stoepfelwerth Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Stoepfelwerth guarantees payment of the plugging fee.

Operator's full Name: Stoepfelwerth Drilling, Incorporated,

Complete Address: Box #193, Russell, Kansas.

Lease Name: Simpson Well No. 1

Location: SW-SE Sec. 10 Twp. 2 Rge. (E)(W) 27

County: Decatur Total Depth 4005' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Stoepfelwerth was instructed to plug the well as follows:

246'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1114'

Circulate hole with heavy mud. Pull DP to 1375' and displace 100 Sx.
cement thru DP. Pull DP to 275' and displace 25 Sx. cement thru DP.
Pull DP, set brodge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

W. L. Nichols
Conservation Division Agent