

State of Kansas



15-039-20293-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian WICHITA, KANSAS 67217

RECEIVED STATE CORPORATION COMMISSION

OCT 21 1974

CONSERVATION DIVISION Wichita, Kansas

10-21-74

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock Administrator 500 Insurance Building Wichita, Kansas 67202

Dear Sir:

Mr. Lowell Moore of G & G Drilling Company has this

date requested permission to plug the following described well:

Mr. Moore guarantees payment of the plugging fee.

Operator's full Name: Dane G Hansen Trust,

Complete Address: Box #187, Logan, Kansas.

Lease Name: Macfee Well No. 1

Location: NW-NW Sec. 8 Twp. 2 Rge. (E)(W) 27

County: Decatur Total Depth 3250' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Moore was instructed to plug the well as follows:

261'--8 5/8" Surface casing, cement circulated with 165 Sx. Top of Dakota section @ 900'.

Circulate hole with heavy mud. Pull DP to 1125' and displace 110 Cu. Ft. cement thru DP. Pull DP to 275' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

[Signature] Conservation Division Agent