



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 1 1971
CONSERVATION DIVISION
Wichita, Kansas
6-1-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Rowe of Slawson Drilling Co., Inc., has this date requested permission to plug the following described well:

Mr. Rowe guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson,

Complete Address: 408 One-Twenty Building, Wichita, Kansas.

Lease Name: Uehlin Well No. A-3

Location: 150'-SE-NE-NW Sec. 7 Twp. 2 Rge. (E)(W) 27

County: Decatur Total Depth 3570' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rowe was instructed to plug the well as follows:

330'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1000'.

Circulate hole with heavy mud. Pull DP to 1250' and displace 100 Sx.
cement thru DP. Pull DP to 350' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

N. L. T. Nichols
Conservation Division Agent