



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 27 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
5-27-71

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Rowe of Slawson Drilling Co., Inc., has this date requested permission to plug the following described well:

Mr. Rowe guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson,

Complete Address: 408 One-Twenty Building, Wichita, Kansas.

Lease Name: Uehlin Well No. C-1

Location: CSW-SE Sec. 6 Twp. 2 Rge. (E)(W) 27

County: Decatur Total Depth 3565' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Rowe was instructed to plug the well as follows:

315'--8 5/8" Surface casing, cement circulated with 250 Sx.  
Top of Dakota section @ 1125'.

Circulate hole with heavy mud. Pull DP to 1350' and displace 100 Sx.  
cement thru DP. Pull DP to 350' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

H. L. Nichols  
Conservation Division Agent