

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24282-00-00
Spot: N2SWSE Sec/Twnshp/Rge: 2-18S-24W
740 feet from S Section Line, 2090 feet from E Section Line
Lease Name: HAAS Well #: 1
County: NESS Total Vertical Depth: 4445 feet

Operator License No.: 5474
Op Name: NORTHERN LIGHTS OIL COMPANY, L
Address: PO BOX 164
ANDOVER, KS 67002

SURF Size: 8.625 feet: 356

#14446

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/18/2004 10:00 PM
Plug Co. License No.: 4958 Plug Co. Name: MALLARD, J. V., INC.
Proposal Rcvd. from: CAROL Company: MALLARD, J. V., INC. Phone: (620) 241-4640

Proposed Plugging Method: 1ST PLUG AT 1720' WITH 50 SX CMT. 2ND PLUG AT 850' WITH 50 SX CMT. 3RD PLUG AT 400' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 15 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: NONE
Date/Time Plugging Completed: 06/19/2004 12:30 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:

Perfs:


1ST PLUG AT 1720' WITH 50 SX CMT. 2ND PLUG AT 850' WITH 50 SX CMT. 3RD PLUG AT 400' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 15 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

RECEIVED
JUN 28 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01



Signed

Jim Holland PART II
(TECHNICIAN)

INVOICED Form CP 100

DATE 6-29-04

INV. NO. 2004061793