

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

19-039-20259-00-00

RECEIVED
STATE CORPORATION COMMISSION

APR 2 1973
4-2-73
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Donald C. Slawson,

Complete Address 408 One-Twenty Building, Wichita, Kansas.

Lease Name Uehlin Well No. C-2

Location App:-CSE-SE- Sec. 6 Twp. 2 Rge. (E) (W) 27

County Decatur Total Depth 3560'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Abercrombie Drilling, Incorporated,

Address 408 One-Twenty Bldg., Wichita, Ks. License No.

Operation Completed: Hour 3:30 PM Day 28 Month 3 Year 1973

The above well was plugged as follows:

316'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 950'.

Circulated hole with heavy mud. Pulled DP to 1175' and displaced 110 Cu. Ft. cement
thru DP from 1175' to 850'. Pulled DP to 340' and displaced 30 Cu. Ft. cement thru DP
from 340' to 265'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED
DATE 4/3/73
INV. NO. 7212-4