

4 060079

4-14

2139

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-039-20,865 -00-00  
N2 SE NE, SEC. 3, T 2 S, R 27 W/EX  
3630 feet from S section line  
650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Lease Name MacFee Well # 1

Operator: Murfin Drilling Co./Douglas MacFee  
Name & Address 250 N. Water, Suite 300  
Wichita, KS 67202

County Decatur 119.60  
Well Total Depth 3680 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 272

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A XXXXX

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling Co. License Number 6033

Address Wichita, KS

Company to plug at: Hour: 3:45PM Day: 14 Month: April Year: 1990

Plugging proposal received from Keith VanPelt

(company name) Murfin Drilling Co. (phone) 316-267-3241

were: Order 190 sxs. 60/40 pos 6% gel 1/4# floccul per ex.

Space all plugs through drill pipe with heavy drilling mud.

Plugging Proposal Received by Herb Deines  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None XXXXXXXX

Operations Completed: Hour: 3:45PM Day: 14 Month: April Year: 1990

ACTUAL PLUGGING REPORT 1st plug at 2125' with 25 sxs. Anhydrite 2108-2139

2nd plug at 1400' with 100 sxs. Dakota 1096-1396'

3rd plug at 325' with 40 sxs. Surface pipe to 272'

4th plug at 40' with 10 sxs. wiper plug at 40'

rathole with 15 sxs.

Remarks: Halliburton Cementing

(If additional description is necessary, use BACK of this form.)

**INVOICED**  
(If you do not observe this plugging.

DATE MAY 5-9-90

WV. NO. 28077

JUN 21 1990

Signed Herb Deines  
(TECHNICIAN)

Herb Deines

Rec'd  
5-1-90

MAY 5-9-90  
28077  
4-14