

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

Form CP-1  
September 2003  
Form must be Typed  
Form must be Signed  
All blanks must be Filled

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

API # 15- 189-22469 <sup>00-00</sup> (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued.

Indicate original spud or completion date 5/4/04

Well Operator: Anadarko Petroleum Corporation KCC License #: 4549  
(Owner/Company Name) (Operator's)

Address: 1201 Lake Robbins Drive City: The Woodlands

State: TX Zip Code: 77380 Contact Phone: 832 636-3128

Lease: Sullivan Well #: B-2 Sec. 26 Twp. 34 R. 39  East  West

CSE SW SE Spot Location/QQQQ County Stevens

330 Feet from (in exact footage)  North /  South (from nearest outside section corner) Line of Section (not Lease Line)

1650 Feet from (in exact footage)  East /  West (from nearest outside section corner) Line of Section (not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well

SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other \_\_\_\_\_  
RECEIVED  
KANSAS CORPORATION COMMISSION  
JUN 24 2004  
CONSERVATION DIVISION  
WICHITA, KS

Conductor Casing Size: N/A Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8-5/8" Set at: 1740' Cemented with: 470 Sacks

Production Casing Size: 5-1/2" Set at: 6538' Cemented with: 220 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perfs:5984'-5990' CIBP @ 6025'

Elevation: 3299' ( G.L.  K.B.) T.D. 6840' PBDT 6498' Anhydrite Depth \_\_\_\_\_  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Bullhead 2 sxs hulls and 20 sxs Class H

cement to plug perfs. Cut off 5-1/2" casing @ free point. Set cement plugs as follows: 50 sxs from

1650' to 1800', 40 sxs from 429' to 550', 10 sxs fro 4' to 40'. Cut off and cap 8-5/8" 4' below GL.

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? ACO-1 is due in September.

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

List Name of Company Representative authorized to be in charge of plugging operations:  
David Releford Phone: 620 482-1012

Address: 1707 W. 2nd City/State Liberal, KS 67901

Plugging Contractor Sargent & Horton Plugging, Inc. KCC License # 31151  
(Company Name) (Contractor's)

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731 Phone: 580 854-6515

Proposed Date and Hour of Plugging (If known?): \_\_\_\_\_

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 6-23-04 Authorized Operator / Agent: Jerry N. Blossom  
(Signature)



RECEIVED  
KANSAS CORPORATION COMMISSION

JUN 24 2004

CONSERVATION DIVISION  
WICHITA, KS

June 23, 2004

Ms. Sharon Ahtone  
Kansas Corporation Commission  
Conservation Division  
130 S. Market-Room 2078  
Wichita, KS 67202-3802

**RE: Form CP-1, Well Plugging Application Form  
Sullivan B-2  
Sec. 26, T34S, R39W  
Stevens County**

Dear Ms. Ahtone:

Please find enclosed a Form CP-1 for the above-mentioned well.

If you need any additional information, please contact me at (832) 636-3128.

Sincerely,

A handwritten signature in cursive script, appearing to read "Jerry N. Blossom".

Jerry N. Blossom  
Staff Environmental & Regulatory Analyst

Enclosure

# KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    John Wine, Commissioner    Robert E. Krehbiel, Commissioner

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Anadarko Petroleum Corporation  
1201 Lake Robbins Drive  
The Woodlands, TX 77380

June 25, 2004

Re: SULLIVAN #B-2  
API 15-189-22469-00-00  
SESWSE 26-34S-39W, 330 FSL 1650 FEL  
STEVENS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888

Sincerely



David P. Williams  
Production Supervisor