

4-7

4- 020129

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API number: 15-039-20,902-0000

SE SW NE /4 SEC. 30, 02 S, 26 W
2970 feet from S section line
1650 feet from E section line

Operator license# 30606

Lease: Stapp Farms Well # 1-30

Operator: Murfin Drilling Company
Address: 250 N. Water
Suite 300
Wichita, Kansas 67202

County: Decatur 122.69
Well total depth 3775 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 260 feet

Aband. oil well _____, Gas well _____, Input well _____, SWD _____, D & A X

Plugging contractor: Murfin Drilling Company License# 30606

Address: Same as above

Company to plug at: Hour: _____ Day: 07 Month: April Year: 1997

Plugging proposal received from: Keith Van Pelt

Company: Murfin Drilling Company Phone: 316 267 3241

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

<u>1st plug @ 2170 feet with 25 sacks</u>	<u>Rat hole: 15 sacks</u>
<u>2nd plug @ 1370 feet with 100 sacks</u>	
<u>3rd plug @ 310 feet with 40 sacks</u>	
<u>4th plug @ 40 feet with 10 sacks</u>	

RECEIVED
KANSAS CORP COM
APR 10 AM '97

Plugging Proposal Received by: Ken Kuhn

4-10-97

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 9:30 AM, Day: 07, Month: April, Year: 1997

Actual plugging report: Hole reported plugged as above.

Order 190 sx 60/40 pozmix w/ 6% gel and 2.0 sx celloflake or flowcel.

Remarks: Allied Cementing performed the cement job.

Condition of casing(in hole): GOOD X BAD _____ Anhy.plug: YES X NO _____
Bottom plug(in place): YES X, CALC _____, NO _____ Dakota plug: YES X, NO _____
Plugged through TUBING _____, CASING X. Elevation: 2619 GL

I did[] / did not[X] observe the plugging.

Ken Kuhn
(agent)
Form CP-2/3

INVOICED
DATE APR 14 1997
INV. NO. 47913
4-7