

6 030576

API NUMBER 15-039-20,779-00-00 ^R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

CNE SW, SEC. 29, T 2 S, R 26 W

1980 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5422

Lease Name CARTER Well # 1

Operator: ABERCROMBIE DRUG. INC.

County DECATUR 128.38

Name & Address 801 UNION CTR.

Well Total Depth 3950 feet

WICHITA, KANSAS

Conductor Pipe: Size _____ feet

67202

Surface Casing: Size 8 5/8 feet 256'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor ABERCROMBIE DRUG. INC. License Number 5422

Address ABOVE

Company to plug at: Hour: AM Day: 26 Month: 9 Year: 19 85

Plugging proposal received from WALLY TOWNES

(company name) ABERCROMBIE DRUG. INC. (phone) _____

were: 8 5/8 SET @ 256' w/170 SX WITH HOLE FULL OF NO LESS THAN 36 UIS. MUD
NO LOSS OR GAIN OF FLUID SPOT CEMENT PLUGS WITH DRILL PIPE
ORDER 200 SX. 60/40 PZ-6 GEL 3/4 8 5/8 W.P. BJ TITAN CMT. CO.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5:30 AM Day: 26 Month: 9 Year: 19 85

ACTUAL PLUGGING REPORT SPOT D.P. @ 2150 BREAK CIRC. DISPLACE 25 SX. CMT MIX
LAYDOWN D.P. TO 1350' DISPLACE 100 SX. CMT MIX. 7 1/2 SX. HULLS LAYDOWN
D.P. TO 275' DISPLACE 40 SX. CMT. MIX. LAYDOWN D.P. PUSH W.P. TO
KELLY DEPTH Dump 1/2 SX. HULLS & 10 SX. CMT MIX. TO BASE CELLAR.
BALLANCE ALL PLUGS w/ ROTARY MUD. DISPLACE 15 SX. IN RATHOLE &
10 SX. IN MOUSEHOLE w/ JOINT OF PIPE. PLUG COMPLETE

Remarks: ARB 3872' ELEV. 2597 GL ANHY 2123-53

(If additional description necessary, use BACK of this form.)

INVOICED

DATE 10-10-85

INV. NO. 10400

NOV 13 1985

OCT 7 1985

10-7-85
CONSERVATION DIVISION
Wichita, Kansas

Signed Carl Goodrow (TECHNICIAN)

33
10-4-85
MMH