

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-20925-00-00
Spot: S2SWSW , Sec/Twnshp/Rge: 20-2S-26W
440 feet from S Section Line, 4670 feet from E Section Line
Lease/Unit Name: HERB SHIRLEY Well Number: 1-20
County: DECATUR Total Vertical Depth: 3800 feet

Operator License No.: 31956
Op Name: DARK HORSE OIL COMPANY
Address: 34681 FOREST PARK DR.
ELIZABETH, CO 80107

Conductor Pipe: Size feet: \$123.50
Surface Casing: Size 8.625 feet: 302
Production: Size feet:
Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 08/17/2002 1:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: KEITH VANPELT Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: ROGER MOSES WitnessType: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 08/17/2002 4:30 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 302'.
1st. Plug at 2160' w/25 sxs. Anhydrite.
2nd. Plug at 1375' w/100 sxs. Dakota Base.
3rd. Plug at 350' w/40 sxs. Base S.P. + 50'.
4th. Plug at 40' w/10 sxs. 8 5/8" wiper plug.
Rathole with 15 sxs cement.
Mousehole with 10 sxs cement.
Total of 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.

RECEIVED
AUG 23 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Roger L. Moses
(TECHNICIAN)

INVOICED

DATE 8-23-02

INV. NO. 2003060374

Form CP-2/3

AUG 21 2002