

KANSAS

4

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20021-06-01

10-7-69
RECEIVED
STATE CORPORATION COMMISSION
OCT 7 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Donald C. Slawson,

Complete Address 408 One-Twenty Building, Wichita, Kansas.

Lease Name Ohms Well No. 1-A

Location SW-SW-SE Sec. 30 Twp. 2 Rge. (E) (W) 26

County Decatur Total Depth 3648'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center Building, Wichita, Kansas. License No. _____

Operation Completed: Hour 2:00 PM Day 4 Month 10 Year 1969

The above well was plugged as follows:

2601--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 1225'.

Circulated hole with heavy mud. Pulled DP to 1150' and displaced 100 Sx. cement thru
DP from 1150' to 1125'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from
275' to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 10/7/69

INV. NO. 600-11