

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20021-00-00

RECEIVED
AUG 16 1967
8-16-67
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Donald C. Slawson,

Complete Address: 408 One-Twenty Building, Wichita, Kansas.

Lease Name Ohms Well No. A-1

Location SW-SW-SE Sec. 30 Twp. 2 Rge. (E) (W) 26

County Decatur Total Depth 2365

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Slawson Drilling Company, Incorporated,

Address: 408 One-Twenty Building, Wichita, Ks License No.

Operation Completed: Hour 5:00PM Day 13 Month 8 Year 1967

The Above well was plugged as follows:

260'--8 5/8" Surface pipe, cement circulated with 175 Sx.
Dakota section from 1200' to 1290'.

Circulated hole with heavy mud. Pulled DP to 1320' and displaced 105 Sx.
cement thru DP. Pulled DP to 280' and displaced 25 Sx. cement thru DP.

Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. A. Nichols
Well Plugging Supervisor

DATE 8/16/67
INV. NO. 6151-W