

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20273-00-00

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
NOV 26 1973
CONSERVATION DIVISION
Wichita, Kansas
11-26-73

Operator's Full Name Empire Drilling Company,

Complete Address 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name Wood Well No. 1

Location SW-SW-SE Sec. 22 Twp. 2 Rge. (E) (W) 26

County Decatur Total Depth 3815'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center, Wichita, Kansas. License No.

Operation Completed: Hour 8:00 PM Day 21 Month 11 Year 1973

The above well was plugged as follows:

29%'-8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1050'.

Circulated hole with heavy mud. Pulled DP to 1275' and displaced 110 Cu. Ft. cement
Thru DP from 1275' to 950'. Pulled DP to 310' and displaced 30 Cu. Ft. cement thru
DP from 310' to 235'. Pulled DP, set bridge @ 40' w ith 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 11/29/73

INV. NO. 8212-W

Signed: W. L. Dickels
Well Plugging Supervisor