

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20264-00-00

RECEIVED
STATE CORPORATION COMMISSION

APR 30 1973

CONSERVATION DIVISION
Wichita, Kansas

4-30-73

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Chief Drilling Company, Incorporated & Bill J. Porter,

Complete Address 905 Century Plaza, Wichita, Kansas.

Lease Name Shirley Well No. 1

Location N/2-N/2-NE Sec. 18 Twp. 2 Rge. (E) (W) 26

County Decatur Total Depth 3664'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Chief Drilling Company, Incorporated,

Address Above License No.

Operation Completed: Hour 3:00 PM Day 27 Month 4 Year 1973

The above well was plugged as follows:

264'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1100'.

Circulated hole with heavy mud. Pulled DP to 1325' and displaced 110 Cu. Ft. cement
thru DP from 1325' to 1000'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 4/30/73
INV. NO. 7306-W