

STATE OF KANSAS
STATE CORPORATION COMMISSION
100 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-159-22,060-00-00

LEASE NAME Carlton E

WELL NUMBER 1

1320 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 24 TWP. 18 RGE. 7W (E) or (W)

COUNTY Rice

Date Well Completed _____

Plugging Commenced 6-3-04

Plugging Completed 6-7-04

RECEIVED
JUN 15 2004

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR CORONADO OIL & GAS, INC.

ADDRESS P.O. Box 1285 Great Bend, Kansas 67530

PHONE#(620) 792-6702 OPERATORS LICENSE NO. 6141

Character of Well Oil

Oil, Gas, D&A, SWD, Input, Water Supply Well

The plugging proposal was approved on _____ (date)

by Virgil Clothier (KCC District Agent's Name).

Is SACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3250'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	218'	None
				4-1/2"	3223'	1800'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid ^{was} placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Plugged off bottom with sand to 2940' and 4 sacks cement. Cut casing loose @1800', pulled up to 950', pumped 35 sacks cement, pulled up to 600', pumped 35 sacks cement w/200% bulls, pulled up to 270', pumped 110 sacks cement and circulated to surface, 60/40 pos, 4% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Coronado Oil & Gas, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 14th day of June, 2004

[Signature]
Notary Public

My Commission Expires: _____

