

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

RECEIVED

JUN 21 2004

KCC WICHITA

15-159-01991-00-00

Form CP-4

September 2003

Type or Print on this Form

Form must be Signed

All blanks must be Filled

Lease Operator: Carl Boxberger Oil, Inc.

Address: P.O. Box 1604 Great Bend, Kansas 67530

Phone: (620) 793-6032 Operator License #: 4707

Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: (Date)

by: Virgil Clothier (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: Bottom: T.D. 2700'

API Number: 15- NA

Lease Name: Habigar

Well Number: 3

Spot Location (QQQQ): SE NE NW

990 Feet from X North / South Section Line

2310 Feet from East / W West Section Line

Sec. 27 Twp. 18 S. R. 10 East X West

County: Rice

Date Well Completed: 10-3-47

Plugging Commenced: 5-27-04

Plugging Completed: 6-1-04

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows show 10" casing at 227' and 7" casing at 2700'.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Set CIBP @2600' with 2 sacks cement on top. Perforated 7" casing @1225', 875' & 280'. Ran tubing to 1225', pumped 50 sacks cement, pulled up to 875', pumped 50 sacks cement, pulled up to 280', pumped 165 sacks cement & circulated to surface on both sides. Pulled tubing & topped off with 50 sacks cement, 60/40 pos, 4% gel. Topped well off again with 45 sacks cement. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529

Address: P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Carl Boxberger Oil, Inc.

State of Kansas County, Rice, ss.


Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Handwritten Signature]

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 18th day of June 20 04

[Handwritten Signature] My Commission Expires: Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten initials]