

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-093-00399000

LEASE NAME Garden City F

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2540 Ft. from S Section Line

2540 Ft. from ~~E~~-Section Line ^{W Per CPA's Rec. Bery 6/10/00}

SEC. 12 TWP. 24 RGE. 35 (or (W

COUNTY Kearny

Date Well Completed 1-9-48

Plugging Commenced 5-13-04

Plugging Completed 5-14-04

LEASE OPERATOR Oxy USA, Inc.

ADDRESS 1701 N. Kansas PO Box 2528 Liberal, KS. 67905

PHONE (620) 629-4200 OPERATORS LICENSE NO. 5447

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well) ^{Per KCC 06/21/03}

The plugging proposal was approved on 5-12-04 (date)

by Kevin Strube (KCC District Agent's Name)

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation Chase Depth to Top 2410 Bottom 2582 T.D. 2726

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	800	-
				5 1/2	2720	648

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging materials were used, state the character of same and depth placed, from feet to feet each section.
Mixed 500 lb. hulls to 35 sx cmt. to plug perfs and anhydrite from 2200 to 1900, pumped mud spacer to 850, 20 sx cmt. 850 to 700, mud to 0. Recovered 648 5 1/2 Circ. hole w/mud 40 sx 648 to 528 10 sx 40 to 0 Cut & capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oxy USA Inc.

STATE OF Kansas COUNTY OF Seward, ss.

(Employee of Operator) or (Operator above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed the same to be true and correct, so help me God.

RECEIVED JUN 25 2004

KCC WICHITA


(Signature) [Signature]

(Address) PO Box 2528 Liberal, KS 67905

SUBSCRIBED AND SWORN TO before me this 23rd day of June, 2004

Anita Peterson

Notary Public



Commission Expires: Oct 1, 2005