

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4

September 2003

Type or Print on this Form

Form must be Signed

All blanks must be Filled

Lease Operator: Bear Petroleum, Inc.

Address: P.O. Box 438 Haysville, Kansas 67060

Phone: (316) 524-1225 Operator License #: 4419

Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: \_\_\_\_\_ (Date)

by: Mike Wilson (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)

\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. 3480'

API Number: 15-159-03808-00-00

Lease Name: Willhaus

Well Number: 2-6

Spot Location (QQQQ): \_\_\_\_\_ - E/2 - SW *NW*

1990 Feet from  North /  South Section Line

990 Feet from  East /  West Section Line

Sec. 6 Twp. 21 S. R. 6 East  West

County: Rice

Date Well Completed: 11-11-58

Plugging Commenced: 6-11-04

Plugging Completed: 6-11-04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	165'	None
				4-1/2"	3473'	1440'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plugged off bottom with sand to 3420' and 4 sacks cement. Cut casing loose @1440', pulled up to 1050', pumped 35 sacks cement W/100# hulls, pulled up to 625', pumped 35 sacks cement W/200# hulls, pulled up to 250' and circulated 100 sacks cement to surface, 60/40 pos, 4% gel.

Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529

Address: P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Bear Petroleum, Inc.

State of Kansas County, Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly


sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 24th day of June, 20 04

Irene Herzberg  
Notary Public My Commission Expires: \_\_\_\_\_



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
JUN 25 2004  
KCC WICHITA

*bw*