

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Decatur County, Sec. 10 Twp. 2S Rge. 27 (E) (W)

Location as "NE/CNW/SW" or footage from lines C/ SW/4, SE/4

Lease Owner Stoepelwerth Drilling, Inc.

Lease Name Simpson Well No. 1

Office Address Box 193, Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 26 19 70

Application for plugging filed June 26 (phone) 19 70

Application for plugging approved June 26 (phone) 19 70


Plugging commenced June 26 19 70

Plugging completed June 26 19 70

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production none 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well W.L. Nichols

Producing formation none Depth to top Bottom Total Depth of Well 4005 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface	water	0	220	8 5/8	249	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Circulated hole from bottom. laid down drill pipe to 1375', Halliburton pumped 100 sx. 50-50poz w/ 6% gel, laid down drill pipe to 275', pumped 25 sx. as above, laid down drill pipe to 40', pumped 10 sx. as above.

RECEIVED
STATE CORPORATION COMMISSION

JUL 6 1970

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services

Address Hayes, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.


George P. Stoepelwerth, II, (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) George P. Stoepelwerth

(Address)

Described and sworn to before me this 29 day of June, 19 70

Anna Starnes Stoepelwerth
Notary Public.



State

DRILLERS LOG

15-039-20162-00-00

STOEPPELWERTH DRILLING, INC
RUSSELL, KANDAS

WELL: #1 Simpson

COMMENCED DRILLING: June 17, 1970

LOCATION: SW/4 SE/4 10-2S-27W
Decatur County, Kansas

COMPLETED DRILLING: June 25, 1970
PLUGGED: June 26, 1970

SURFACE CASING: 8 5/8" @ 249' with 175 sx. 50-50 Pozmix

FOOTAGE	FORMATION
0- 220	Surface sand and clay
220- 1145	Shale
1145- 2180	Sand and shale
2180- 2220	Anhydrite
2220- 2925	Sand and shale with streaks of Limestone
2925- 3470	Limestone and shale with streaks of sand
3470- 3730	Limestone and shale
3730- 3905	Limey and sandy shale
3905- 3985	Dolomite and sandy dolomite
3985- 3998	Sand
3998- 4005	Granite
4005=TD	

DRILLING TIME: Min. per 2 feet																									
3200-50	6	6	5	6	5	5	7	8	5	7	7	11	10	8	7	7	8	8	9	7	6	6	5	6	6
3250-00	7	7	7	6	5	4	5	3	5	5	5	7	6	7	5	7	6	5	9	10	11	8	7	9	11
3300-50	10	7	7	6	5	6	5	5	5	6	5	7	9	5	6	6	6	7	5	4	6	3	3	6	6
3350-00	8	7	7	8	6	5	5	3	5	6	5	5	5	5	5	6	5	7	6	6	6	7	6	6	7
3400-50	5	6	6	6	8	6	4	5	4	5	14	4	7	6	7	7	6	7	7	5	5	8	8	9	8
3450-00	8	6	6	7	9	7	6	6	6	5	6	7	7	7	5	6	4	4	10	6	7	7	7	6	6
3500-50	5	6	7	9	10	8	9	7	6	8	8	9	8	7	2	3	4	7	6	5	11	11	9	9	9
3550-00	10	10	12	13	11	6	9	10	10	10	9	16	14	9	6	7	10	9	6	5	6	5	6	6	7
3600-50 **	7	8	7	7	9	8	10	11	7	8	10	8	8	12	12	9	8	6	8	8	7	9	8	8	8
3650-00 **	11	8	8	6	9	9	7	12	13	12	9	9	8	15	13	13	7	12	13	10	11	15	13	13	14
3800-50	12	14	12	13	12	13	14	15	15	10	11	14	14	11	13	12	9	10	16	15	16	14	15	14	27
3850-00	12	15	17	13	8	14	16	16	14	14	10	10	15	16	14	5	11	12	6	4	6	8	4	7	10
3900-50	14	16	12	12	10	15	14	13	13	16	13	15	16	12	13	8	7	7	10	11	8	7	7	7	6
3950-00	7	9	8	8	9	9	6	8	6	4	5	6	7	7	9	9	8	7	5	8	8	4	13	20	26
4000-05	27	33	(1 ft) 18		* Trip for new bit																				
**3650-3700	10	9	7	5	6	7	8	6	6	5	7	8	10	13	9	11	12	11	8	8	8	11	10	10	6
3700-3750	7	7	6	7	9	11	10	9	13	13	10	12	10	10	8	3	7	7	4	7	9	10	12	13	9

I hereby certify that the above and foregoing is a true and accurate report of the drilling of the well described.

DATE: June 29, 1970

G.P. Stoepfelwerth, II
G.P. Stoepfelwerth, II

State of Kansas
County of Russell

RECEIVED
STATE CORPORATION COMMISSION

Subscribed and sworn before me, a Notary Public, this 29th day of June, 1970

JUL 6 1970
CONSERVATION DIVISION
Wichita, Kansas

G.P. Stoepfelwerth, II

My Commission expires April 9, 1972

