

15-039-20259-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Decatur County Sec. 6 Twp. 2S Rge. (E) 27 (W)
Location as "NE/CNW/SW" or footage from lines. SE SE
Lease Owner Donald C. Slawson
Lease Name UEHLIN "C" Well No. 2
Office Address 408 One Twenty Bldg., Wichita, Ks. 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 28, 1973
Application for plugging filed (verbally) March 28, 1973
Application for plugging approved (verbally) March 28, 1973
Plugging commenced March 28, 1973
Plugging completed March 28, 1973
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3560 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FRGM	TD	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug set at 1175' w/110 cu. ft. cement
2nd plug set at 340' w/30 cu. ft. cement
3rd plug set at 40' w/10 cu. ft. cement
Plug down at 3:30 p.m. 3-28-73.

RECEIVED
STATE CORPORATION COMMISSION
APR 3 1973
CONSERVATION DIVISION
Wichita, Kansas

4-3-73

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.
Address 801 Union Center, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Jerry A. Langrehr (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jerry A. Langrehr
801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of March, 1973

My commission expires February 10, 1975
Beverly Mann Notary Public

CONTRACTOR'S WELL LOG

15-039-20259-00-00

OPERATOR: Donald C. Slawson
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: UEHLIN "C" #2
 LOCATION: SE SE Sec. 6-2S-27W
 Decatur County, Kansas
 GEOLOGIST: Don Strong
 SPUD DATE: March 21, 1973
 COMPLETION DATE: March 28, 1973

0	100	Clay & Sand
100	160	Sand
160	209	Sand and Shale
209	712	Shale
712	1600	Shale & Sand Streaks
1600	2008	Lime & Shale
2008	2040	Anhydrite
2040	2605	Shale
2605	2620	Flint
2620	3355	Lime and Shale
3355	3560	Lime
	3560	Rotary Total Depth

Drilled 326' of 12 1/2" surface hole, set 8 jts. of 8-5/8" sfs. csg. at 324' K.B. w/ 225 sx. HA-5 cement. Plug was down 3-21-73.
 Dry and Abandoned

SAMPLE TOPS
 Anhydrite 2008 (+ 496)
 B/Anhydrite 2040 (+ 464)

ELEVATION
 2504 K.B.

RECEIVED
 STATE CORPORATION COMMISSION
 APR 3 1973
 CONSERVATION DIVISION
 Wichita, Kansas
 4-3-73

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jerry A. Langrehr, Vice President of Abercrombie Drilling, Inc. does hereby state that the above and foregoing is a true and correct copy of the log of the UEHLIN "C" #2, SE SE, Section 6-2S-27W, Decatur County, Kansas.

ABERCROMBIE DRILLING, INC.

By: Jerry A. Langrehr
 Jerry A. Langrehr
 Vice President

Subscribed and sworn to before me, a Notary Public, in the for the aforesaid county and state as of this 2nd day of April, 1973.

Beverly Manry
 Beverly Manry, Notary Public

My Commission Expires:

February 10, 1975