

State of Kansas



15-039-20021-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
AUG 16 1967
8-16-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bill Rowe of Slawson Drlg. Co. Inc., has this date requested permission to plug the following described well:

Mr. Rowe guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson,

Complete Address: 408 One-Twenty Building, Wichita, Kansas.

Lease Name: Ohms Well No. A-1

Location: SW-SW-SE Sec. 30 Twp. 2 Rge. (E)(W) 26

County Decatur Total Depth 2365 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rowe was instructed to plug the well as follows:

260'--8 5/8" Surface pipe, cement circulated with 175 Sx. Dakota section from 1200' to 1290'.

Circulate hole with heavy mud. Pull DP to 1320' and displace 105 Sx. cement thru DP. Pull DP to 280' and displace 25 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

H. L. Nichols

Conservation Division Agent