

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Messenger Petroleum Inc.  
Address: 525 S. Main, Kingman, KS 67068  
Phone: (620) 532-5400 Operator License #: 4706  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: \_\_\_\_\_ (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-095-21503-00-00  
Lease Name: M C Simon  
Well Number: 1  
Spot Location (QQQQ): \_\_\_\_\_ - NW - NE - SE  
2310 Feet from  North /  South Section Line  
990 Feet from  East /  West Section Line  
Sec. 9 Twp. 30 S. R. 7  East  West  
County: Kingman  
Date Well Completed: \_\_\_\_\_  
Plugging Commenced: 5-29-04 6-1-04 <sup>KCC</sup> 6/29/04  
Plugging Completed: 6-1-04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	213	
				4 1/2	4196	2800

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Checked hole sand at 4020', bailed 4 sacks of portland, pulled slips, ripped 2960', no gain, ripped to 2800', worked free, pulled to 1250', pumped 35 sacks, pulled to 750', pumped 35 sacks, pulled to 260', pumped 130 sacks, circulated to surface.

RECEIVED

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925  
Address: 401 West Main, Lyons, KS 67554

JUN 28 2004

Name of Party Responsible for Plugging Fees: Messenger Petroleum Inc.  
State of Kansas County, Kingman, ss.

KCC WICHITA

Jon F. Messenger (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Jon F. Messenger  
(Address) 525 S. Main Kingman, KS 67068

SUBSCRIBED and SWORN TO before me this 29th day of June, 2004

John M. Wood  
Notary Public  
JOHN M. WOOD  
NOTARY PUBLIC  
STATE OF KANSAS  
My Commission Expires: 9/9/2006

Mail to: KCC - Conservation Division, 1808 Market Room 2078, Wichita, Kansas 67202

# Quality Well Service, Inc.

401 West Main  
Lyons, KS 67554

# Invoice

Date	Invoice #
6/16/2004	552

Bill To
Messenger Petroleum, Inc. 525 South Main Kingman, KS 67068

P.O. No.	Terms	Lease Name
	net	MC Simon

Description	Qty	Rate	Amount
Rig Time	14	135.00	1,890.00T
Sand	1	35.00	35.00T
Ripping Pipe	2	140.00	280.00T
Water Truck	2	60.00	120.00T
Backhoe	1	62.00	62.00T
5-28-04 Rigged up, checked hole, sanded bottom, loaded hole, dug cellar, tore head down.			
6-1-04 Checked hole sand at 4020', bailed 4 sacks of Portland, set floor, pulled slips, ripped 2960', no gain, ripped 2800', worked free, pulled to 1250', pumped 35 sacks, pulled to 750', pumped 35 sacks, pulled to 260', pumped 130 sacks cement, circulated to surface, layed rest of pipe down, tore down.			
<b>Subtotal</b>			\$2,387.00
<b>Sales Tax (6.3%)</b>			\$150.38
<b>Total</b>			\$2,537.38

RECEIVED  
JUN 28 2004  
KCC WICHITA