

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-039-20927-00-00  
Spot: NWSEW Sec/Twnshp/Rge: 14-2S-27W  
3745 feet from S Section Line, 3715 feet from E Section Line  
Lease/Unit Name: LONG RANCH Well Number: 5  
County: DECATUR Total Vertical Depth: 3760 feet

Operator License No.: 31956  
Op Name: DARK HORSE OIL COMPANY  
Address: 34861 FOREST PARK DR.  
ELIZABETH, CO 80107

Conductor Pipe: Size feet: 8/22.20  
Surface Casing: Size 8.625 feet: 330  
Production: Size feet:  
Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 12/23/2002 5:00 PM

Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: KEITH VANPELT Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 6% gel with /14# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 12/23/2002 9:00 PM

KCC Agent: HERB DEINES

**Actual Plugging Report:**

1st. Plug at 2175' w/25 sxs. Anhydrite 2163' - 2196'.  
2nd. Plug at 1450' w/100 sxs. Dakota 1130' - 1430'.  
3rd. Plug at 330' w/40 sxs. Surface pipe 280'  
4th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

RECEIVED  
1-3-2003  
JAN 03 2003  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

  
(TECHNICIAN)

**INVOICED**

Form CP-2/3

DATE 1-6-03

INV. NO. 2003061038

DEC 31 2002