

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-20918-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 14-2S-27W
2970 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: LONG RANCH Well Number: 4
County: DECATUR Total Vertical Depth: 3800 feet

Operator License No.: 31956
Op Name: DARK HORSE OIL COMPANY
Address: 12543 N HWY 83 STE 228
PARKER, CO 80134

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 309
Production: Size feet:
Liner: Size feet:

\$123.50

Well Type: DH UIC Docket No: Date/Time to Plug: 02/16/2001 12:30 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: BILL WINN Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 6% gel - 1/4# floseal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT STAAB Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 02/16/2001 2:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

1st. Plug at 2200' w/25 sxs. Middle of Anhydrite.
2nd. Plug at 1400' w/100 sxs. Dakota Base.
3rd. Plug at 368' w/40 sxs. Base of surface pipe.
4th. Plug at 40' w/10 sxs - 8 5/8" wiper plug.
Rathole with 15 sxs.
Mousehole with 10 sxs.

INVOICED
DATE 03-07-2001
INV. NO. 2001010223

2-22-2001


Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

MS.

Signed



(TECHNICIAN)

FEB 20 2001