

2-4

4-061044

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-039-20,901 00-00  
NW NW SE /4 SEC. 14, 02 S, 27 W  
2310 feet from S section line  
2310 feet from E section line

Operator license# 30606 Lease Long Well # 1-14  
Operator: Murfin Drilling Company, Inc. County: Decatur 121.55  
Address: 250 N. Water - Suite #300 Well total depth 3740 feet  
Wichita, Kansas 67202 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 278 feet

Aband. oil well , Gas well , Input well , SWD , D & A   
Plugging contractor: Murfin Drilling Company, Inc. License# 30606  
Address: Wichita, Kansas 67202

Company to plug at: Hour: 9:45 A.M. Day: 4 Month: February Year: 1997  
Plugging proposal received from: Keith VanPelt  
Company: Murfin Drillin Company Phone: \_\_\_\_\_

Were: Order 190 sxs 60/40 posmix - 6% gel with 1/4# floseal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines  
Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 11:45 A.M., Day: 4, Month: February, Year: 1997

Actual plugging report:  
1st. Plug at 2160' w/25 sxs. Anhydrite 2146' - 2178'.  
2nd. Plug at 1420' w/100 sxs. Dakota 1111' - 1411'.  
3rd. Plug at 330' w/40 sxs. Surface pipe at 278'.  
4th. Plug at 40' w/10 sxs.  
15 sxs in rathole.

Remarks: Allied Cementing.  
Condition of casing(in hole): GOOD  BAD  Anhy.plug: YES  NO   
Bottom plug(in place): YES , CALC , NO  Dakota plug: YES , NO   
Plugged through TUBING , CASING . Elevation: 2611 GL

I did[  ] / did not[  ] observe the plugging.

[Signature]  
(agent)  
Form CP-2/3

**INVOICED**  
DATE FEB 14 1997  
INV. NO. 47577

STATE CORPORATION COMMISSION  
FEB 11 1997  
2-11-97  
CONSERVATION DIVISION  
Wichita, Kansas