

Conservation Division  
Wichita State Office Bldg.  
130 S. Market, Room 2078  
Wichita, KS 67202

C.A.R.-82-3-117

15-039-0055500-01

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

API NUMBER ocket # E-21, 265

LEASE NAME Pelkey

WELL NUMBER #1

990 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 16 TWP. 2 RGE. 27 (E) or (W)

COUNTY Decatur

Date Well Completed 2-26-1954

Plugging Commenced 8-27-97

Plugging Completed 8-27-97

LEASE OPERATOR Baird Oil Co. Inc.

ADDRESS Box 428 Logan, KS 67646

PHONE # (913) 689-7456 OPERATORS LICENSE NO. 5352

Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8/21/97 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? NA

Producing Formation Kansas City Depth to Top 3508 Bottom 3708 T.D. 3628

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface	sand + shale	Surface	211	8 5/8	211	None
Kansas City	shale + limestone	Surface	3611	5 1/2	3611	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set

Pumped 50 SKS of 60/40 Pozmix with 10% Gel down backside with a shut-in pressure of 366#. Then pumped down the casing (5 1/2") with 250 SKS of 60/40 poz-mix with 10% gel and 500# of hulls. Initial shut-in pressure was 606#

Name of Plugging Contractor Allied Cementing Co. Inc. License No. \_\_\_\_\_

Address P.O. Box 31 Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Baird Oil Co Inc., Box 428, Logan, KS

STATE OF Kansas COUNTY OF Phillips, ss. 67646


I Jim R. Baird - Employee of Operator (Employee of Operator) or (Operator) o above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jim R. Baird

(Address) Box 428 Logan, KS 67646

Subscribed AND SWORN TO before me this 27th day of August, 19 97

Robert B. Hartman  
Notary Public



My Commission Expires: 3/29/99  
USE ONLY ONE SIDE OF EACH FORM