

15-039-20381-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Decatur County, Sec. 31 Twp. 2S Rge. 27W /E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SE/4 NE/4 SE/4

Lease Owner Cities Service Oil Company
Lease Name Miller "Z" Well No. 1
Office Address 700 Sutton Place Bldg., Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____
D & A



Locate well correctly on above
Section Plat

Date Well completed April 23, 1977
Application for plugging filed April 23, 1977
Application for plugging approved April 23, 1977
Plugging commenced April 23, 1977
Plugging completed April 23, 1977
Reason for abandonment of well or producing formation _____
D & A

If a producing well is abandoned, date of last production 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 14,143
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	269'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug #1 @ 1300' w/70 sx cement
Plug #2 @ 240' w/20 sx cement
Bridge @ 40' w/10 sx cement
5 sx cement in rathole
Cement - 50-50 Pozmix, 6% Gel

RECEIVED

MAY 04 1977

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

5-4-77

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company
1720 KSB&T Building, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss. contractor
Gloria Fawcett (employee of ~~xxxxxxx~~)


of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gloria Fawcett
1720 KSB&T Building, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of April, 1977.

My commission expires _____

Joyce A. Hagermann
Notary Public.



15-039-20381-00-00

DRILLERS LOG

No. 1 Miller "Z"

CASING RECORD:
8 5/8" @ 274'
w/200 sx cement

COMPANY: Cities Service Oil Company
CONTRACTOR: Red Tiger Drilling Company
COMMENCED: April 7, 1977
COMPLETED: April 23, 1977

DESCRIPTION:
SE/4 NE/4 SE/4
Sec. 31-T2S-R27W
Decatur County, Kansas

TOTAL DEPTH: 4,143'

ELEVATION: 2,652' KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Post Rock & Shale	0	284	
Shale	284	1337	
Hard Sand	1337	1346	
Shale	1346	1750	
Shale & Red Bed	1750	1972	
Sand	1972	1985	
Shale	1985	2030	
Sand	2030	2111	
Shale	2111	2314	
Anhydrite	2314	2346	
Shale	2346	2500	
Shale & Lime Streaks	2500	2630	
Shale & Lime	2630	2737	
Shale	2737	2845	
Shale & Lime	2845	3092	
Lime	3092	3175	
Shale & Lime	3175	3280	
Lime	3280	3680	
Lime (Coring)	3680	3762	
Lime	3762	3947	
Lime & Shale	3947	3990	
Lime	3990	4143	
RTD		4143	

RECEIVED
STATE CORPORATION COMMISSION

MAY 04 1977
5-4-77
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett
Gloria Fawcett

Subscribed and sworn to before me this 26th day of April, 1977.

Joyce A. Hagermann
Notary Public

