

4-080228

TO:

6-18

API number: 15- 039-20,910-0000

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, ROOM #2078
WICHITA, KANSAS 67202-3802

W2 SE NE NE /4 SEC: 24- 2 - 27 W
1250 Feet from N (N/S) Line
400 Feet from E (E/W) Line

Operator License# 31956

LEASE: Long Ranch B WELL # 1-24

Operator: Dark Horse Oil

County: DECATUR

Address: 12543 North Hwy83
Parker Colo.
80134-8800

Well total Dept 3750 feet
Conductor Pipe inch @ feet
Surface pipe 8 5/8 inch @ 264 feet

Aband. Oil Wel Gas Well Input Well SWD: D & A: X

Pluggin contractor: Murfin Drilling Co. License#: 30606

Address: Wichita, Kansas

Company to plug at: Hour: ?? Day: Month: Year:

Plugging proposal received from Keith VanPelt

Company: Murfin Drilling Co. Phone:

Were: Spot plugs through drill pipe w/ heavy mud between all plugs

1 st plug 2130 feet with 25 sacks Rat hole: 15 sacks
2nd plug @ 1220 feet with 100 sacks Mouse hole: sacks
3rd plug @ 315 feet with 40 sacks Wiper plug @ 40 foot
4th plug 40 feet with 10 sacks
5th plug feet with sacks

Plugging proposal recived by: Bruce Basye
Pluggings operations attended by agent? All [], Part [], None [X]

Completed Hour: 05:15 AM Day: 18 Month: June Year: 1998

Actual plugging report: Hole reported plugged as above.
Order 190 sx 60/40 Posmix w/ 6% gel and 40 sx celloflake or flowcel.

MAILED
JUN 26 1998
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Elevation: 2616 GL, Anhydrite top: 2120 feet Anhy. plug: Y

Dakota plug: Y Bottom plug in place B

Plugged through drill pipe Y

Arbuckle top Cemented by: Allied Cementing Co.

I did [] did NOT [X] observe the plugging.

Bruce Basye

Bruce Basye
(agent)

INVOICED

DATE 7-2-98

INV. NO. 50858