

4-032405

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-039-20,894-0000
238'E.of
NW NE NE /4 SEC. 16, 02, 27 W
4950 feet from S section line
1082 feet from E section line

3/29

115.54

Operator license# 8981
Operator: Adeco & Chambers, Inc.
Address: P.O. Box 873
Hays, Kansas 67601

Lease: Chambers Well # D-5
County: Decatur
Well total depth 3555 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 210 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 29 Month: March Year: 2000

Plugging proposal received from: Dean Ives

RECEIVED
KANSAS CORPORATION COMMISSION

Company: Adeco & Chambers, Inc. Phone: -

Were: Order 275 sxs 60/40 pozmix - 10% gel - 500# hulls.

APR 06 2000
4-6-2000
CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All , Part , None

Completed: Hour: 11:00 A.M., Day: 29 Month: March, Year: 2000

Actual plugging report: 8 5/8" set at 210' w/175 sxs cwc. 5 1/2" set at 3575' w/125 sxs.
Port collar set at 2100' with 350 sxs. Squeezed 5 1/2" with 275 sxs cement blend with 500#
hulls to Max. P.S.I. 300#. Test 8 5/8" to 500#. Backside is full. Plug completed.
Prod. Perf at 3300'.
This well was completed and never used.

Remarks:
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: _____ GL

I did / did not observe the plugging.

Carl Goodrow
(agent)

INVOICED
DATE 4/7/00
INV. NO. 061522

Form CP-2/3

(Handwritten signature/initials)