


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-039-00057-00-0a
WELL PLUGGING RECORD



Locate well correctly on above Section Plat

DECATUR County. Sec. 15 Twp. 2 Rge. 27 (E) (W) W
Location as "NE/CNW/SW" or footage from lines SW SW SW
Lease Owner E. K. CARBY, DRILLING CO & H. E. ZOLLAR
Lease Name MONAGHAN Well # 1
Office Address Box, 620 McPherson, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 7-30-52 19____
Application for plugging filed 7-24-61 19____
Application for plugging approved 19____
Plugging commenced August 1 1961 19____
Plugging completed 19____
Reason for abandonment of well or producing formation _____
Not enough to produce
If a producing well is abandoned, date of last production 7-31-1961 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation K.C. Lime Depth to top _____ Bottom _____ Total Depth of Well 4015 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				<u>85/8 @253'W/150</u>	<u>sax</u>	<u>None</u>
				<u>51/2 @3658'</u>	<u>w/100</u>	<u>sax</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGED BACK TO 3653' WITH ROCK, DUMPED 5 SAX. CEMENT. SHOT AND PULLED PIPE. MUD TO 233', SET ROCK BRIDGE INTO SURFACE PIPE. FILLED SURFACE PIPE WITH REDY MIX CEMENT TO TOP OF PIPE.

RECEIVED
STATE CORPORATION COMMISSION
OCT 6 1961
CONSERVATION DIVISION
Wichita, Kansas

10-6-61

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor HERT SELF CASING PULLING CO.
Address R.R. # 4, HUTCHINSON KANSAS

STATE OF _____, COUNTY OF _____, ss.

_____, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Hert Self
R.R. # 4 Hutchinson Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 2 day of Oct, 1961

Clara J. Bishop
Notary Public.

My commission expires July 31 - 1965



DRILLER'S

15-039-00057-00-02

L G G

MONAGHAN #1. 2

Company: The E. K. Carey Drilling Co., Inc., & H. E. Roller

Contractor: Peal Brothers, Inc.

Farm: Monaghan Well No. 1
Comm: 7-17-52 Comp: 7-30-52

Sec. 15, Twp. 2, Rge. 27,

Total Depth: 4015'

County: Decatur,
Kansas

Casing: 8 5/8" 238' con.
5 1/2" 3685' con.

Elevation: 2608 K.B.

Production:

Figures below indicate bottom of formations

Clay and Soil	0'	95
Sand		128
Shale		145
Sand		170
Shale		725
Shale and Sand		1685
Shale and Pyrite		1740
Shale		1790
Shale and Red Bed		2060
Shale and Shells	Shot #1. 2150' Shot #2. 2200' Shot #3. 1850' Shot #4. 1650'	2145
Anhydrite		2165
Anhydrite		2180
Shale and Shells		2400
Shale & Shells & Bentonite streaks		2570
Shale and Shells		2750
Shale and Lime Shells		2850
Shale and Lime Streaks		2905
Lime and Shale		3375
Lime		3450
Lime and Shale		3480
Lime		3795
Shale and Lime Streaks		3845
Lime		3978
Granite Wash		4009
Granite		4015
Total Depth		4015

RECEIVED
STATE CORPORATION COMMISSION
OCT 17 1961
CONSERVATION DIVISION
Wichita, Kansas
10-17-61

This is to certify that the above information is to the best of my knowledge true and correct.

PEAL BROTHERS, INC.,

By: Wendell E. Peal

SUBSCRIBED AND SWORN to before me this 30th day of July, 1952.

Bernice G. Jewison
Notary Public - Barton County, Kansas

My commission expires April 23, 1955.