

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Noble Energy, Inc.  
Address: 100 Glenborough Dr., #100, Houston, TX, 77067  
Phone: (281) 872-3100 Operator License #: 33190  
Type of Well: D&A Docket #: \_\_\_\_\_  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other)* *(If SWD or ENHR)*  
The plugging proposal was approved on: 5/8/2004 (Date)  
by: Jacob Pfeifer (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
Smokey Hills (Niobrara) Depth to Top: 1480' Bottom: 1519' T.D. 39'  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 023-20552-00-00  
Lease Name: Zimbelman  
Well Number: 44-31  
Spot Location (QQQQ): S - E - S - E  
660 Feet from  North /  South Section Line  
660 Feet from  East /  West Section Line  
Sec. 31 Twp. 3 S. R. 41  East  West  
County: Cheyenne  
Date Well Completed: 5/8/2004  
Plugging Commenced: 5/8/2004 *KCC*  
Plugging Completed: 5/9/2004 *July 4*

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Smokey Hills (Niobrara)	Gas & Water	1480'	1519'	20#, 7"	255' set @ 261'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged well with 60/40 Poz. Mix Cement with 6% Gel & 1/4 Flo-Cele as follows: Plug #1: 50 sx Cement from 1440' - 1165' (275'), Plug #2: 40 sx Cement from 370' - 160' (210'), and Plug #3: 10 sx Cement from 45' - 5' (40') with wiper plug.

Name of Plugging Contractor: Excell Drilling Company License #: 8273  
Address: P.O. Box 305, Wray, CO, 80758-0305

Name of Party Responsible for Plugging Fees: Noble Energy, Inc.  
State of Texas County, Harris, ss.

Janis L. Vercher, Sr. Regulatory Specialist (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



PATSY J. NEVILL (Signature) Jan L Vercher

NOTARY PUBLIC, STATE OF TEXAS Address) 100 Glenborough Dr., #100, Houston, TX, 77067

MY COMMISSION EXPIRES NOV 28 2004

SUBSCRIBED and SWORN TO before me this 15th day of June, 2004


Patsy J. Nevill My Commission Expires: 11-28-2004  
Notary Public

RECEIVED

JUN 21 2004

KCC WICHITA

*Jan*



**CEMENTER'S WELL SERVICE, INC.**  
 P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE  
**183925**

Date <u>05-08-04</u>	Well Owner <u>Noble Energy, Inc</u>	Well No. <u>44-31</u>	Lease <u>Zimbleman</u>
County <u>cheyenne</u>	State <u>KANSAS</u>	Field	
Charge to <u>Excell Drilling Company</u>	Charge Code		For Office Use Only
Address <u>Rt # 2</u>	City, State <u>Wray, Colorado 80758</u>		
Pump Truck No. <u>1206</u>	Code	Bulk Truck No. <u>1217</u>	Code
Type of Job	Depth	Ft.	To
Surface	Bottom of Surface	Ft.	To
Plug <u>3 1/2" DR.</u>	Plug Landed @	Ft.	Time On <u>23:30</u>
Production	Pipe Landed @	Ft.	Time Off <u>02:15</u>

Reference No.	Description	Qty.	Meas.	Unit Price	Amount
	Pump Truck Charge				
	Cement Neat				
	Poz. Mix <u>60/40</u>	<u>100</u>	<u>SKC</u>		
	Calcium Chloride				
	Gel <u>6 % Flo-Cele 1/4 #Per Sack</u>				
	Handling Charge				
	Hauling Charge				
	Additional Cement				
	<u>1<sup>st</sup> Plug @ 11:39 - W/ 50 SKC</u>				
	<u>2<sup>nd</sup> Plug @ 200' 1/2 in 1/2 OUT of Surface casing W/ 40 SKC</u>				
	<u>3<sup>rd</sup> Plug @ 40' Top of Surface casing</u>				
	<u>Mixing R. T. B. B. - Displacement R. T. C. R. P. 1/2</u>				

RECEIVED  
 JUN 21 2004  
 KCC WICHITA

Remarks:	Tax Reference Code	Sub Total
	<u>KS 4.9%</u>	Tax
	Disc.	Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1206</u>	Pump Truck			<u>60</u>		<u>30</u>	
<u>1217</u>	Bulk Truck			<u>60</u>		<u>30</u>	

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Loan, Randy, Lucie Received By Don Drannon  
 Customer or His Agent