

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01703-00-00
Spot: NESESW Sec/Twnshp/Rge: 32-9S-19W
990 feet from S Section Line, 2970 feet from E Section Line
Lease Name: LYND Well #: 2
County: ROOKS Total Vertical Depth: 3760 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

PROD Size: 5.5 feet: 3756
SURF Size: 8.625 feet: 160

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/30/2004 1:30 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: JOE STRUBE Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: Ordered out 400 sxs 60/40 pozmix - 10% gel - 600# hulls.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/30/2004 6:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Hit hard bridge at 1902' - decided to P&A.
Perforated casing at 1900' - 1650' - 1000'.
TIH with tubing to 1850' - mixed and pumped 150 sxs cement with 150# hulls.
Pulled up to 800' - circulated cement with 150 sxs cement with 150# hulls.
POOH. Topped with 100 sxs cement and 300# hulls. S.I.P. 350#.
Hooked up to the annulus - instant 500# pressure.

Perfs:


RECEIVED
JUL 06 2004
KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

JUL 01 2004

TOMLINSON-KATHOL #2 LYND 32-9-19W
 NE SE SW
 Contr. TOMLINSON-KATHOL ROOKS County
 E 2226 RB Comm. Comp. 2-24-61 IP 50 BOPD

Tops	Depth	Datum
TOP	3207	-981
HEEB	3414	-1188
TOR	3433	-1207
LANS	3452	-1226
B/KC	3654	-1428
CONG	3688	-1462
ARB	3754	-1528
TD	3760	-1534

Casing
 8" 160
 5" 3756
 40'-102'
 DST 3492-3554/1 HR, 935' SW,
 BHP 1100-1080#/30"
 CO 3760: FU 900' 0/13 HRS

LYND WEST POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS