

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01707-00-00
Spot: N2S2SW Sec/Twnshp/Rge: 32-9S-19W
990 feet from S Section Line, 3960 feet from E Section Line
Lease Name: LYND Well #: 7
County: ROOKS Total Vertical Depth: 3734 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

PROD Size: 5.5 feet: 3733
SURF Size: 8.625 feet: 156

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/30/2004 10:00 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: JOE STRUBE Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: Ordered out 400 sxs 60/40 pozmix - 10% gel - 600# hulls.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/30/2004 1:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Hit hard bridge at 1580' - decided to P&A.
Perforated casing at 1580' and 1000'.
TIH with tubing to 1550' - mixed and circulated cement with 175 sxs cement and 600# hulls.
POOH. Topped with 225 sxs cement. S.I.P. 300#.
Hooked up to the annulus - instant 500# pressure.

Perfs:

RECEIVED
JUL 06 2004
KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING.

Plugged through: TBG

District: 04

Signed

Jay Pfeifer
(TECHNICIAN)

JUL 01 2004


TOMLINSON-KATHOL #7 LYND 32-9-19W
N2 S2 SW

Contr. TOMLINSON-KATHOL ROOKS County

E 2201 RB Comm. Comp. 10-6-61 IP 36 BOPD/ARB LM

Tops	Depth	Datum	Casing
TOP	3182	-981	8" 156
HEEB	3389	-1188	5" 3733
TOR	3408	-1207	CO 3734: SWB 80 80/4 HRS
LANS	3425	-1224	
CONG	3666	-1465	
ARB	3732	-1531	
ID	3734	-1533	

LYND WEST POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS