

KANSAS

*4*

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 15 1969

15-039-20132-00-00

CONSERVATION DIVISION  
Wichita, Kansas  
12-15-69

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Stoeppelwerth Drilling, Incorporated,  
Complete Address Box #193, Russell, Kansas.  
Lease Name Shirley Well No. 1  
Location SW-SW Sec. 12 Twp. 2 Rge. (E) (W) 27  
County Decatur Total Depth 3934  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor Above  
Address        License No.         
Operation Completed: Hour 5:45 PM Day 10 Month 12 Year 1969

The above well was plugged as follows:

247'--8 5/8" Surface casing, cement circulated with 165 Sx.  
Top of Dakota section @ 1100'.  
        
Circulated hole with heavy mud. Pulled DP to 1325' and displaced 100 Sx. cement thru  
DP from 1325' to 1000'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from  
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.  
        
      

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Nichols*  
Well Plugging Supervisor

INVOICED  
DATE 12/15/69  
INV. NO. 1044-W