

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
**Type or Print on this Form
Form must be Signed
All blanks must be Filled**

Lease Operator: Noble Energy, Inc.
 Address: 100 Glenborough Dr., #100, Houston, TX, 77067
 Phone: (281) 872-3100 Operator License #: 33190
 Type of Well: D&A Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 5/8/2004 (Date)
 by: Jacob Pfeifer (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
Smokey Hills (Niobrara) Depth to Top: 1480' Bottom: 1519' T.D. 39' 1067
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 023-20552-00-00
 Lease Name: Zimbelman
 Well Number: 44-31
 Spot Location (QQQQ): S - E - S - E
660 Feet from North / South Section Line
660 Feet from East / West Section Line
 Sec. 31 Twp. 3 S. R. 41 East West
 County: Cheyenne
 Date Well Completed: 5/8/2004
 Plugging Commenced: 5/8/2004 *KCC BEN 5/8/04*
 Plugging Completed: 5/9/2004

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface Conductor & Production) | | | | |
|---------------------------|-------------|--|-------|---------|-----------------|------------|
| Formation | Content | From | To | Size | Put In | Pulled Out |
| Smokey Hills (Niobrara) | Gas & Water | 1480' | 1519' | 20#, 7" | 255' set @ 261' | 0' |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged well with 60/40 Poz. Mix Cement with 6% Gel & 1/4 Flo-Cele as follows: Plug #1: 50 sx Cement from 1440' - 1165' (275'), Plug #2: 40 sx Cement from 370' - 160' (210'), and Plug #3: 10 sx Cement from 45' - 5' (40') with wiper plug.

RECEIVED

Name of Plugging Contractor: Excell Drilling Company License #: 8273
 Address: P.O. Box 305, Wray, CO, 80758-0305

JUN 2 1 2004

KCC WICHITA

Name of Party Responsible for Plugging Fees: Noble Energy, Inc.
 State of Texas County, Harris, ss.

Janis L. Vercher, Sr. Regulatory Specialist (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Signature]
 Patsy J. Nevill
 NOTARY PUBLIC, STATE OF TEXAS
 MY COMMISSION EXPIRES NOV 28, 2004
 Address) 100 Glenborough Dr., #100, Houston, TX, 77067

SUBSCRIBED and SWORN TO before me this 15th day of June, 20 04

[Signature] My Commission Expires: 11-28-2004
 Notary Public