

STATE OF KANSAS
STATE CORPORATION COMMISSION
100 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-159-22,043-00-00

LEASE NAME ALMQUIST A

WELL NUMBER 4

RECEIVED
JUN 15 2004
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div. office within 30 days.

2970-330 Ft. from S^N Section Line
2970-330 Ft. from E Section Line

LEASE OPERATOR CORONADO OIL & GAS, INC.

SEC. 4 TWP. 19 RGE. 6W (E) or (W)

ADDRESS P.O. Box 1285 Great Bend, Kansas 67530

COUNTY Rice

PHONE#(620) 792-6702 OPERATORS LICENSE NO. 6141

Date Well Completed _____

Character of Well Oil

Plugging Commenced 6-7-04

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6-9-04

The plugging proposal was approved on _____ (date)

by Mike Wilson (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 3200'

Show depth and thickness of all water, oil and gas formations.

WELL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	212'	None
				4-1/2"	3168'	1847'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from _____ feet to _____ feet each set. Plugged off bottom with sand to 3030' and 4 sacks cement. Cut casing loose @1847', pulled up to 900', pumped 35 sacks cement with 200# hulls, pulled up to 550', pumped 35 sacks cement with 200# hulls, pulled up to 265', pumped 100 sacks cement and circulated to surface. 60/40 pos. Plugging Complete. 4% gel.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Coronad Oil & Gas, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 14th day of September, 20 04

Irene Herzberg
Notary Public

My Commission Expires:

