

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: K & N Petroleum, Inc.

Address: 513 West 6th Street, Ellinwood, Kansas 67526

Phone: (620) 564-3422 Operator License #: 3208

Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: June 21st, 2004 (Date)

by: District 2 - No KCC agent on location (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)

_____	Depth to Top: <u>3066'</u>	Bottom: <u>3381'</u>	T.D. <u>3383'</u>
_____	Depth to Top: _____	Bottom: _____	T.D. _____
_____	Depth to Top: _____	Bottom: _____	T.D. _____

API Number: 15 - 159 - 21,739 - 00 - 00

Lease Name: Oberle

Well Number: #2

Spot Location (QQQQ): NE NW

660 Feet from  North /  South Section Line

990 Feet from  East /  West Section Line

Sec. 16 Twp. 19 S. R. 10  East  West

County: Rice

Date Well Completed: 12/14/1983

Plugging Commenced: 6/22/04

Plugging Completed: 6/23/04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	0'	503'	8-5/8"	503'	0'
	Production	0'	3376'	5-1/2"	3376'	1542.19'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

M.I.R.U. Got sand, trailer, jacks and knife. Brackeen spotted sand - 50 bbls. total fluid-let sand fall. Spot 5 sx cement on bottom. Spot in jacks. Pulled casing out of slips-pulled stretch. Set up cement and water. Cut casing @1550' - pulled to 1250' - pumped 35 sx & 2 bags of hulls. Pulled to 900' - pumped 35 sacks cement with 200# hulls. Pulled to 500'-circulated cement to surface with 130 sx cement. Tore down and moved off.

Name of Plugging Contractor: D. S. & W. Well Servicing, Inc. License #: 6901


Address: P.O. Box 231, Claflin, Kansas 67525

Name of Party Responsible for Plugging Fees: K & N Petroleum, Inc.

State of Kansas County, Barton, ss.

Edward S. Nemnich (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

 KAREN J. MITCHELL  
Notary Public - State of Kansas  
My Appt Expires 4/13/06

(Signature) Edward S. Nemnich

(Address) P.O. Box 231, Claflin, Ks. 67525

SUBSCRIBED and SWORN TO before me this 28th day of June, 20 04

Karen J. Mitchell  
Notary Public

My Commission Expires: 4/13/06

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*[Handwritten mark]*