

RECEIVED

JUN 30 2004

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

KCC WICHITA

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

151-11009-00-02

Lease Operator: BEREN CORPORATION

Address: P O BOX 20380, WICHITA, KS 67208

Phone: (316) 265-3311 Operator License #: 5634

Type of Well: ENHR Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: (Date)

by: (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet) SIMP DOL Depth to Top: 4332 Bottom: 4350 T.D. SIMP SD Depth to Top: 4369 Bottom: 4392 T.D.

API Number: 15 - SPUD 2/1959

Lease Name: NRSU

Well Number: 8

Spot Location (QQQQ): - NW - NE - SW

2310 Feet from North / South Section Line

3630 Feet from East / West Section Line

Sec. 30 Twp. 27 S. R. 12 East West

County: PRATT

Date Well Completed: MARCH 1959

Plugging Commenced: MAY 19, 2004

Plugging Completed: MAY 20, 2004

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out)

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

CHECKED HOLE SAND @4260', BAILED 5 SACKS OF PORTLAND, RIPPED TO 2600', WORKED PIPE, RIPPED 2220', WORKED FREE, PULLED TO 720', PUMPED 50 SACKS, PULLED 330', PUMPED 50 SACKS, PULLED TO 40', PUMPED 10 SACKS, PULLED LAST JOINT.


Name of Plugging Contractor: QUALITY WELL SERVICE, INC. License #: 31925

Address: 401 WEST MAIN, LYONS, KS 67554

Name of Party Responsible for Plugging Fees: BEREN CORPORATION

State of KANSAS County, SEDGWICK, ss.

GARY MISAK (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Gary Mick

(Address) BEREN CORP., P O BOX 20380, WICHITA, KS 67208

SUBSCRIBED and SWORN TO before me this 28TH day of JUNE, 20 04

Diana E Plotner My Commission Expires: Aug 10, 2007 Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION**
Please TYPE Form and File ONE Copy

JUN '04 2004

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued.

indicate original spud or completion date 2/59

Well Operator: BEREN CORP KCC License #: 5634
(Owner / Company Name) (Operator's)

Address: BOX 20380 City: WICHITA

State: KS Zip Code: 67208 Contact Phone: (316) 265 - 3311

Lease: NRSU Well #: 8 Sec. 30 Twp. 27 S. R. 12 East West

 - NW - NE - SW Spot Location / QQQQ County: PRATT

2310 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

3630 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well

SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8 Set at: 324 Cemented with: 250 Sacks

Production Casing Size: 5 1/2 Set at: 4492 Cemented with: 150 Sacks

List (ALL) Perforations and Bridgeplug Sets: CIBP 4180 4332-37 SIMP

Elevation: 1877 (G.L. / K.B.) T.D.: 4492 PBTD: _____ Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): AS KCC REQUIERS

Sand 4260 + 55K5

RECEIVED

JUN 30 2004

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? NOT AVAILABLE TO US

KCC WICHITA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: JASON

Phone: (316) 265 - 3311

Address: BOX 20380 City / State: WICHITA KS

Plugging Contractor: QUALITY WELL SERVICE KCC License #: 31925

Address: 401 W MAIN LYONS KS 67554 Phone: (620) 727 - 3410
(Company Name) (Contractor's)

Proposed Date and Hour of Plugging (if known?): ASAP

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: _____ Authorized Operator / Agent: _____
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

109cl 720 5088 330 5088
40 10885

440-0065

Copy

Quality Well Service, Inc.

**401 West Main
Lyons, KS 67554**

JUN 04 2004

Invoice

Date	Invoice #
6/2/2004	546

Bill To
Beren Corp. Box 20380 Wichita, KS 67208

P.O. No.	Terms	Lease Name
	net	NRSU

Description	Qty	Rate	Amount
Rig Time	17	135.00	2,295.00T
Trucking Floor	1	90.00	90.00T
Sand	1	35.00	35.00T
Cement	5	9.00	45.00T
Ripping Pipe	2	140.00	280.00T
Water Truck	2	60.00	120.00T
Backhoe	1	62.00	62.00T
Out of Town		120.00	120.00T
Phone Calls		7.50	7.50T
Clerical		10.00	10.00T
Wipping Rubber		15.00	15.00T
5-19-04 Drove to well, dug cellar, rigged up, checkd hole, sanded bottom, loaded hole, tore casing head down, set floor, pulled slips, tore head off, checked hole sand at 4260', bailed 5 sacks of portland, ripped 2600', worked pipe, ripped 2220', worked pipe free, pulled to 720'.			
5-20-04 Pumped 50 sacks, pulled to 330', pumped 50 sacks, pulled to 40', pumped 10 sacks, pulled last joint, tore down, loaded out, filled cellar in.			
Subtotal			\$3,079.50

**RECEIVED
JUN 30 2004
KCC WICHITA**

Sales Tax (6.3%)	\$194.01
Total	\$3,273.51

ALLIED CEMENTING CO., INC.

PO BOX 31
 RUSSELL KS 67665
 PH (785) 483-3887
 FAX (785) 483-5566
 FEDERAL TAX ID# 48-0727860

JUN 0 12

JUN 0 1

 *
 * INVOICE *
 *

Invoice Number: 093294

Invoice Date: 05/24/04

Berex

Sold ~~Berexco, Inc.~~
 To: P. O. Box 723
 Hays, KS
 67601

Will File

Cust. I.D.....: Berex
 P.O. Number...: NRSU #8
 P.O. Date.....: 05/24/04

Due Date.: 06/23/04
 Terms : Net 30

Item I.D./Desc.	Qty. Used	Unit	Price	Net	TX
Common	66.00	SKS	7.6500	504.90	T
Pozmix	44.00	SKS	4.0000	176.00	T
Gel	16.00	SKS	11.0000	176.00	T
Handling	126.00	SKS	1.2500	157.50	T
Mileage min. chg.	1.00	MILE	125.0000	125.00	T
Plug	1.00	JOB	500.0000	500.00	T
Mileage pmp trk	2.00	MILE	4.0000	8.00	T

All Prices Are Net, Payable 30 Days Following
 Date of Invoice. 1 1/2% Charged Thereafter.
 If Account CURRENT take Discount of \$ *175.94*
 ONLY if paid within 30 days from Invoice Date

Subtotal: 1647.40
 Tax..... 112.02
 Payments: 0.00
 Total...: 1759.42

RECEIVED
 JUN 30 2004
 KCC WICHITA

ALLIED CEMENTING CO., INC.

15359

Federal Tax I.D.# ~~XXXXXXXXXX~~

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
M.C.

DATE <u>5-20-04</u>	SEC <u>30</u>	TWP <u>27s</u>	RANGE <u>12w</u>	CALLED OUT <u>7⁰⁰ AM</u>	ON LOCATION <u>8⁰⁰ AM</u>	JOB START <u>9⁰⁰ AM</u>	JOB FINISH <u>10³⁰ AM</u>
LEASE <u>NRSU</u>	WELL # <u>8</u>	LOCATION <u>54 + Pratt E. to 30th Rd. 1/4 N</u>			COUNTY <u>Pratt</u>	STATE <u>KS</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)			E. Side				

CONTRACTOR Quality Well Service

TYPE OF JOB ohp

HOLE SIZE 7 7/8" T.D. _____

CASING SIZE 5 1/2" DEPTH 70-330-40

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX 100 MINIMUM 50

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

OWNER Berexco, Inc

CEMENT

AMOUNT ORDERED 110sx 60:40:6
10sx Gel

COMMON	<u>66</u>	A	@	<u>7.65</u>	<u>504.90</u>
POZMIX	<u>44</u>		@	<u>4.00</u>	<u>176.00</u>
GEL	<u>16</u>		@	<u>11.00</u>	<u>176.00</u>
CHLORIDE			@		

EQUIPMENT

PUMP TRUCK CEMENTER Mike Rucker

372 HELPER Mark Brungardt

BULK TRUCK

353 DRIVER Josh McDowell

BULK TRUCK

_____ DRIVER _____

HANDLING	<u>126</u>	@	<u>1.25</u>	<u>157.50</u>
MILEAGE	<u>2 x 126 x .05</u>			<u>125.00</u>
				<u>Min Charge -</u>
				TOTAL <u>1139.40</u>

REMARKS:

1st Plug: 720

9⁰⁰ AM load hole 10sx Gel, 9¹⁰ AM Mix 50sx 60:40:6 @ 13.8 weight Disp. with 11 bbl fresh.

2nd Plug: 330-9³⁵ AM load hole with fresh mix 50sx 60:40:6 @ 13.8 weight, Disp. with 1 bbl fresh

3rd Plug 40' load hole 10⁰⁰ Mix 10sx 60:40:6 @ 13.8 weight Disp. 1/2 bbl fresh

SERVICE

DEPTH OF JOB	<u>720'</u>			
PUMP TRUCK CHARGE				<u>500.00</u>
EXTRA FOOTAGE		@		
MILEAGE	<u>2</u>	@	<u>4.00</u>	<u>8.00</u>
PLUG		@		

TOTAL 508.00

CHARGE TO: Berexco, Inc

STREET _____

CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

	@		
	@		
	@		
	@		

TOTAL _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____

TOTAL CHARGE ~~1139.40~~

DISCOUNT ~~1139.40~~ IF PAID IN 30 DAYS

SIGNATURE Richard O. [Signature]

PRINTED NAME _____

**ANY APPLICABLE TAX
WILL BE CHARGED
UPON INVOICING**