

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-039-20734-00-00

API NUMBER 15,039-20,734

LEASE NAME Olive Waterfl

WELL NUMBER Tr.2-W3

SPOT LOCATION SE NW SW

SEC. 12 TWP. 23 RGE. 28 (X) of ()

COUNTY Decatur

Date Well Completed _____

Plugging Commenced 4-3-85

Plugging Completed 4-15-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR John O. Farmer, Inc.

ADDRESS Box 352, Russell, Ks. 67665

PHONE # (913)-483-3144 OPERATORS LICENSE NO. 5135

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Six

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing formation _____ Depth to top _____ bottom _____ T.D. 3610'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	206'	None
				4-1/2"	3574'	1,236.91'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Dumped 4 sacks cement on bottom, sanded back to 3400' and dumped 4 sacks ceme
Shot casing at 1800', 1500' and 1250'. Pulled 30 joints of 4-1/2" casing.
Squeezed well with 4 sacks hulls, 25 sacks gel, 100 sacks cement, 15 sacks
gel, released plug and pumped 70 sacks 50/50 pozmix cement with 6% added gel
and 3% calcium chloride. Maximum pressure was 200 psi and shut in 100 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111
Address Box 698, Gt. Bend, Ks. 67530

RECEIVED
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Barton, ss.

APR 19 1985
4-19-85
CONSERVATION DIVISION
Wichita, Kansas

James W. Rockhold (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says:
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) James W. Rockhold
James W. Rockhold
(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 17th day of April, 1985

STATE NOTARY PUBLIC
KANSAS
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-87

My Commission expires:

Iona M. Leatherman
Notary Public

NOV 28 1984

15-039-20734-00-00

WELL DATA FOR CASING PULLER

Company: John O. Farmer, Inc

Name of Well: Oliver water flood TR 2-113

Legal Description: SE, NW, SW Sec. 12-25-28W

Directions to Well: McCarton Co., KS
From Overlin KS - 6 mi. east & 4 mi north
& 1/4 mi east then north on (local road)

Date Well was Drilled: Nov. 84

Casing: 206 ft - 8 5/8" w/ 150 A/S
4 1/2" - 10' w/ 150 A/S.

T.D. of Hole: 3610'

Perforations: 3457'-60' w/ 4 holes/ft

Drillers Log: attached

Pumper's Name: Black jeans
ph. 308-375-4389

RECEIVED
STATE CORPORATION COMMISSION

DEC 04 1984
12-4-84
CONSERVATION DIVISION
Wichita, Kansas