


STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Decatur County, Sec. 12 Twp. 2 Rge. 28 (E) W (W)  
Location as "NE/CNWxSWx" or footage from lines C SW NE  
Lease Owner Rock Island Oil & Refining Co., Inc.  
Lease Name Reeves Well No. 1  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19\_\_  
Application for plugging filed 19\_\_  
Application for plugging approved 19\_\_  
Plugging commenced 12-23-64 19\_\_  
Plugging completed 12-28-64 19\_\_  
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3650 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	215'	None
				7"	3839'	1095'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 3640', pushed plug to 3250', sanded to 3200' and dumped 5 sacks of cement @ 3200' with dump bailer. Pulled 7" casing, bridged hole @ 300' and dumped 5 yards of ready mix and 10 sacks of cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 11 1965  
1-11-65  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING COMPLETE.

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss. Noel J. Knight (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of January, 1965

My commission expires May 20, 1968 Notary Public.

WELL LOG

15-039-00515-00-00 R

COMPANY **Rock Island Refining Company**

SEC. 12 T. 25 R. 28W

FARM **REEVES** NO. **One**

LOC. **C/SW NE**

TOTAL DEPTH **3939'**

COUNTRY **Decatur KANSAS**


COMM. **4/23/62**

COMP. **5/4/62**

SHOT OR TREATED **No**

CONTRACTOR **Murfin Drilling Company**

ISSUED



CASING

20 10 **3/4" 215' with 125 sacks cement**

15 8 ~~5000~~

ELEVATION **2488' KB**

12 6

13 5

PRODUCTION **Oil**

**7" 3839' with 175 sacks cement**

FIGURES INDICATE BOTTOM OF FORMATIONS

- 70' Shale & Sand
- 1040' Shale
- 1270' Shale-Sand
- 1725' Shale & Shells
- 2058' Shale-Sand-Red Bed
- 2091' Anhydrite
- 2475' Shale-Shells
- 2880' Shale & Lime
- 3142' Lime & Shale
- 3640' Lime
- 3677' Shale & Lime
- 3825' Shale-Lime-Sand
- 3900' Arbuckle
- 3932' Arbuckle & Granite Wash
- 3943' Rotary Total Depth

ELECTRIC LOG TOPS:

Lansing/Kansas City	3371'
Arbuckle	3828'
Granite Wash	3904'
Granite	3912'
Total Depth	3939'

DST #1 3355'-3385' Open 1 hr. Recovered 10' Oil Cut Mud, 1' Free Oil. FBHP 40#/20 min.

DST #2 3390'-3420' Open 1 hr. Shut In 20 min. Recovered 200' mud, 700' muddy salt water. IF 40# FF 415# FBHP 985#/20 min.

DST #3 3430'-3460' Open 1 hr. Shut In 20 min. Recovered 180' Heavy Oil Cut Mud, 270' oil, 300' gas. IF 20# FF 190# FBHP 1045#/20 min.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 11 1965  
1-11-65  
CONSERVATION DIVISION  
Wichita, Kansas

State of Kansas  
County of Sedgwick } ss:

I, Fred Murfin of the Murfin Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the REEVES#1 well.

Subscribed and sworn to before me this 15th day of May 19 62

My Commission Expires: June 14, 1964

*Fred Murfin*  
*May Kew Blume*  
NOTARY PUBLIC